

Building Department Inspections

Code	Description
BIA	Foundation (pre-pour)
BIAA	Pier Footing
BIAB	Monolithic Slab (Found/slab - 1 pour)(pre-pour)
BIB	Slab (after foundation)
BICC	Ceiling Cover (Ceiling Structure)
BICF	Commercial Fire Caulk
BICW	Concrete Wall
BID	Framing (includes trades on resid.)
BIDS	Pre Demo (verifies utilities are disconnected)
BIDW	Dry Wall (Screw Pattern)
BIE	Insulation
BIFC	Fill Cell (Concrete Blocks)
BIFF	Window Flashing/Fastenings
BIFJ	Floor Joist (Off grade floor frame)
BIFW	Rated Wall (Fire)
BIG	Pool Steel
BIGG	Structural Steel (Buildings)
BIH	Columns
BIHA	Handicap Accessibility (Comm)
BII	Fire Place
BIJ	Roof Dryin
BIL	Nailing (walls)
BILL	Lath
BIP	Pilaster
BIPD	Pool Deck
BIPP	Pool Plumbing Pressure
BIPS	Pool Safety (alarms & fencing/prior to filling)
BIRF	Roof Flashing
BIRL	Roof Nailing
BIRO	Roof over (shingles/metal on shingles prior to start)
BIRT	Retaining Wall
BIS	Status/Info (Use this only if your inspection isn't available)
BISA	Stem Wall

BITB	Tie Beam/Bond Beam
BIWB	Roof Water Barrier (secondary)
BIWD	Window/Door Installations
BFF	Building Final
AFF	Decal Verification
EIA	Temp Pole
EIB	Rough Electric (done w/frame on resid.)
EIC	Electric Ceiling Cover
EID	Electrical Wall Cover
EIF	Temp Power/Equip Check (early power for const)
EIG	Pool Grounding
EIPB	Pool Bonding
EIS	Electrical Status
EIUG	Service Lateral (underground electrical service)
EIUR	Electrical Work Under Slab
EFDR	Electrical Disconnect & Reconnect
EFF	Electrical Final
HIA	Duct Work/Rough (Done w/Frame on Resid)
HIB	Air Test
HIC	Gas Piping
HICURB	Mech Roof Curb
HID	Range Hood
HIE	HVAC Duct Insulation
HIRP	Press Test on Refrig Lines
HIS	HVAC Status
HFF	HVAC Final
PIA	Rough Plumbing (under slab)
PIB	Top Out Plumbing (done w/Frame on resid)
PIS	Plumbing Status
PIST	Sewer Tap
PFF	Plumbing Final
PPA	Private Provider Audit